

OFFICE OF THE CHIEF ENGINEER (W), CAD, BIKANER

NO.T.1522/CE/CAD/CDM/ 67

DATE 21.4.2017


CORRIGENDUM NO 4

As per powers delegated to undersigned and after recommendation of B.S.R. Committee, this corrigendum no.4 as per enclosed sheet is issued for CAD (West), Bikaner Basic Schedule of Rates w.e.f. August 2012 applicable to CAD Projects of Sidhmukh Nohar Irrigation Project and Amar Singh Sub Branch Projects. The corrigendum no.4 shall be as a modification to the original B.S.R., August 2012 as follows:-

1. The Chapter VII (c) is now inserted in the B.S.R. masonry / concrete and plaster with 100% Bajri and using mechanical mixer for SNIP and ASSB projects.

These orders shall come into force with immediate effects.

Encl.: One Sheet table VII (C)


Chief Engineer (W),
CAD, Bikaner.

NO.T.1522/CE/CAD/CDM/ 68-97

DATE 21.4.17

Copy submitted/forwarded to the following for information and necessary action :-

1. The Commissioner, Area Development, Bikaner.
2. Financial Advisor, CAD, (W), Bikaner.
3. Superintending Engineer, CAD, Gnag Nahar OFD Circle, Shriganganagar.
4. Superintending Engineer, CAD Circle, Hanumangarh.
5. Superintending Engineer, CAD, OFD Bhakra Circle, Hanumangarh.
6. Superintending Engineer, CAD, OFD Circle, IGNP, Bikaner.
7. Superintending Engineer, CAD, F.T. (v) & Q.C., Suratgarh.
8. Superintending Engineer, CAD, WR Circle, Shriganganagar / Nohar.
9. Executive Engineer, CAD..... Dn.....
10. Executive Engineer, WR Dn.....
11. Chief Accounts Officer, O/o the CE (W), CAD., Bikaner.
12. ~~D&M and CDM Section, O/o the CE (W), CAD., Bikaner.~~


CHIEF ENGINEER (W)

CHAPTER – VII (C)

Masonry, Concrete and Plaster Works

S.No.	Nomenclature	Unit	ASSB/SNIP (Rate in Rs.)
1	Brick masonry in cement mortar (1:5) including cost of all materials including mechanical mixing of mortar with all leads & lifts and stacking etc. complete in all respect	Cum	2839
2	Brick masonry in cement mortar (1:6) including cost of all materials including mechanical mixing of mortar with all leads & lifts and stacking etc. complete in all respect	Cum	2848
3	Cement concrete (1:4:8) including cost of all materials including using mechanical mixer with aggregate size 40mm with all leads & lifts and stacking etc. complete in all respect	Cum	1786
4	10mm thick Cement plaster in cement mortar (1:4) as per design and specification including cost of all materials including mechanical mixing of mortar with all leads & lifts and stacking etc. with curing for specified period complete in all respect	10 Sqm	565
5	8mm thick Cement plaster in cement mortar (1:6) as per design and specification including cost of all materials including mechanical mixing of mortar with all leads & lifts and stacking etc. complete in all respect	10 Sqm	411

Note:- The complete item rates are inclusive of all leads & lifts, stacking & cost of all materials including cost of OPC Cement (43 Grade)